

ROOM FINISH SCHEDULE

ROOM NO	ROOM NAME	FLOOR		BASE MATL	BASE FINISH	WALLS						CEILING		REMARKS				
		MATL	FIN			NORTH		SOUTH		EAST		WEST						
						MATL	FIN	MATL	FIN	MATL	FIN	MATL	FIN					
100	FOYER	VCT		RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9			
101	CHP	VCT		RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	A
102	RECORDS	VCT		RUBBER		GLUB	2/9	GLUB	2/9	GLUB	2/9	GLUB	2/9	GLUB	2/9	GLUB	2/9	A
103	MEDICATION	VCT		RUBBER		GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	2/9	A
104	STAFF	VCT		RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	AC
105	IT	CONC	5			GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	B
106	SPRINKLER	CONC	5			GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	
107	BEDRM	VCT	6	RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	AC
108	ELEC	CONC	5			GLUB	10/11	GLUB	10/11	GLUB	10/11	GLUB	10/11	GLUB	10/11	GLUB	10/11	
109	BEDRM	VCT	6	RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	AC
110	BEDRM	VCT	6	RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	AC
111	BEDRM	VCT	6	RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	AC
112	BEDRM	VCT	6	RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	AC
113	BEDRM	VCT	6	RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	AC
114	STOR	CONC	5			GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	
115	HOUSE STOR	CONC	5			GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	
116	OT PT	VCT		RUBBER		GLUB	2/9	GLUB	2/9	GLUB	2/9	GLUB	2/9	GLUB	2/9	GLUB	2/9	
117	ACTIVITY	VCT	6	RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	AC
118	LIVING	VCT	6	RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	AC
119	SCREENED PORCH	CONC		RUBBER		C5	13	GLUB	15	C5	13	GLUB	15	C5	13	C5	13	C
120	DINING	VCT	6	RUBBER		GLUB	18/14	GLUB	18/14	GLUB	1/8	GLUB	18/14	GLUB	18/14	GLUB	2/9	C
121	POUNDER	CT	4	CT	4	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	1/8	A
122	CORRIDOR	VCT	6	RUBBER/SHOE		GLUB	1/8	GLUB	1/8	GLUB	17/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	CD
123	KITCHEN	VCT	6	RUBBER		GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	2/9	
124	PANTRY	VCT		RUBBER		GLUB	2/9	GLUB	2/9	GLUB	2/9	GLUB	2/9	GLUB	2/9	GLUB	2/9	
125	TOILET	CT	6/11	CT	4	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	1/8	AC
126	COATS	VCT	6	RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	
127	TOILET	CT	6/11	CT	4	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	1/8	AC
128	JANITOR	CONC	5			GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	
129	LINEUP	VCT		RUBBER		GLUB	2/9	GLUB	2/9	GLUB	2/9	GLUB	2/9	GLUB	2/9	GLUB	2/9	
130	TOILET	CT	6/11	CT	4	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	3/8	GLUB	1/8	AC
131	STAIR	FLY/CONC	5			GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	A
132	LAUNDRY CLOSETS	VCT		RUBBER		GLUB	1/8	GLUB	1/8	GLUB	17/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	CD
133	CORRIDOR	VCT	6	RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	
134	CORRIDOR	VCT	6	RUBBER		GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	1/8	GLUB	2/9	CD
135	HOTER STOR	CONC	5	RUBBER		GLUB	10/16	GLUB	10/16	GLUB	10/16	GLUB	10/16	GLUB	10/16	GLUB	1/8	
200	ATTIC	FLY/UD																

FINISH MATERIALS

GLUB	GYPSUM WALL BOARD	CT	CERAMIC TILE
C5	CEMENTICIOUS SIDING	TILE	TILE (QUARRY)
15	INSECT SCREEN	CONC	CONCRETE
RUBBER	RUBBER BASE (6" TALL)	VCT	VINYL COMPOSITION TILE
FLY	PLYWOOD (UNPAINTED)		


FINISH NOTES:

1. SERVICE LATEX
2. FLAT LATEX PAINT
3. EXPOUT PAINT
4. THIN SET TILE
5. CONCRETE SEALER
6. 2 COLOR FLOOR PATERN
1. FERT TEMP HDBD WANSKOT
8. LEVEL 5 GUB FINISH
9. LEVEL 4 GUB FINISH
10. LEVEL 3 GUB FINISH
11. FREE CODE GUB
12. EXTER RESISTANT GUB
13. EXTERIOR PAINT SYSTEM
14. ONE PICE CHAIRSAIL W/ PAINT WANSKOT BELOW
15. WOOD SHOE BASE SEE DETAIL
16. 4"-Ø" HIGH FTD A/C FLYUD WANSKOT
17. THICK SET FLOOR TILE

REMARKS:

- A. PROVIDE ACOUSTICAL INSULATION @ INTERIOR WALLS
- B. PROVIDE 3/4" X 4" X 8" COX PL YUD
- C. COORDINATE W/ REFLECTED CEILING PLAN
- D. SEE INTERIOR ELEVATIONS FOR MIXED WALL BASE IN CORRIDORS


WINDOW TYPES




WINDOW NOTES

1. WINDOWS SHALL BE VINYL INSULATING UNITS AS MANUFACTURED BY SIKONTON WINDOW PRO-FINISH CONTRACTOR SERIES W/ J CHANNEL REMOVED OR AN APPROVED EQ.
2. PROVIDE INSECT SCREENS AT ALL OPERABLE SASHES
3. PROVIDE WINDOWS W/ NAILING FLANGE
4. ALL GLAZING SHALL BE INSULATED W/ A 5 YEAR WARRANTY AGAINST FOGGING.
5. PROVIDE SMOKE GRAY GLASS AT FIXED SASHES & PERHULL UNITS AT THE FACTORY.
6. PERHULL UNITS AT THE FACTORY.

DETAIL B1 SCALE: 1 1/2" = 1'-0"




DETAIL C2 SCALE: 1 1/2" = 1'-0"



FRAME TYPES



DOOR TYPES



DOOR ABBREVIATIONS

ETI	INSUL	TEMP	ET	HB	FR	WD	PAIR	WOOD	HOLLOW METAL	PRE-HUNG	SOLID CORE	HOLLOW CORE	STYLE & RAIL
ETI	INSUL	TEMP	ET	HB	FR	WD	PAIR	WOOD	HOLLOW METAL	PRE-HUNG	SOLID CORE	HOLLOW CORE	STYLE & RAIL

1. DOOR # 10 NOT USED
2. SEE DOOR HARDWARE SCHEDULE SHEET A002 AND A003

DOOR AND FRAME SCHEDULE

MARK	DOOR					FRAME					NOTES	
	TYPE	WIDTH	LEAF SIZE	HEIGHT	MATERIAL	THK	CORE	GLZ	FRAME			
									WIDTH	TYPE		ELEV
100	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
102	E	2'-6"		6'-8"	HB	1/8"	HC			PH	4	
103	FG	FR 3'-0"		6'-8"	HM	1/34"	NBL	TI	1 3/4	HM	2	TI
104	FG	FR 2'-6"		6'-8"	HM	1/34"	NBL	TI	1 3/4	HM	2	TI
105	FG	FR 2'-6"		6'-8"	HM	1/34"	NBL	TI	1 3/4	HM	2	TI
106	SD	FR 3'-0"		6'-8"	UD	1/8"	9R	IS				
107	FG	FR 2'-6"		6'-8"	HM	1/34"	NBL	TI	1 3/4	HM	2	TI
108	FG	FR 2'-6"		6'-8"	UD	1/34"	NBL	TI	1 3/4	HM	2	TI
109	FG	3'-0"		6'-8"	HM	1/34"	9R	ET	1 3/4	HM	2	T
110	FG	FR 3'-0"		6'-8"	HM	1/34"	NBL	TI	1 3/4	HM	2	TI
111	F	3'-0"		6'-8"	HB	1/34"	NBL		4 1/2	PH	4	TI
112	E	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
113	F	3'-0"		6'-8"	UD	1/34"	9R	ET	4 1/2	HM	2	
114	FG	3'-0"		6'-8"	UD	1/34"	NBL		4 1/2	HM	4	
115	F	FR 2'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
116	F	FR 2'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
117	F	FR 2'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
118	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
119	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
120	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
121	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
122	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
123	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
124	F	3'-0"		6'-8"	HB	1/8"	9C		4 1/2	PH	4	
125	F	FR 2'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
126	F	FR 2'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
127	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
128	F	FR 2'-6"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
129	F	FR 2'-6"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
130	F	2'-8"		6'-8"	UD	1/34"	9C		5 3/4	PH	3	
131	F	3'-0"		6'-8"	UD	1/34"	9C		4 1/2	PH	4	
132	F	FR 3'-0"		6'-8"	HM	1/34"	HC		5 3/4	HM	3	
133	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
134	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
135	E	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
136	F	3'-0"		6'-8"	HM	1/34"	NBL		4 1/2	PH	4	TI
137	F	FR 2'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
138	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	TI
139	FC	3'-0"		6'-8"	HM	1/34"	NBL	ET	1 3/4	HM	2	TI
140	F	FR 2'-6"		6'-8"	HM	1/34"	NBL		1 3/4	HM	2	
141	F	FR 2'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
142	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
143	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
144	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
145	F	FR 3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
146	F	FR 2'-6"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
147	F	3'-0"		6'-8"	HM	1/34"	9C		5 3/4	PH	3	
148	F	3'-0"		6'-8"	HB	1/8"	HC		4 1/2	PH	4	
149	FG	3'-0"		6'-8"	HM	1/34"	NBL	ET	1 3/4	HM	1	ET

FINISH SCHEDULE



SEPTEMBER 03, 2008

BROGDEN LANE  
ICE / MR HOME  
FOR HNN CSB

HUDSON + ASSOCIATES  
A R C H I T E C T S  
120 WEST QUEENS WAY SUITE 201  
(757) 722-1864  
HARRISON, VA  
22669



JOB NUMBER 0704

A3.01